8th St. Bike Access to GT Campus



Alex D'Antoni, George Doyle, Clara Jennings, Karri Thomas

Georgia Capital Planning Tech & Space Management

December 4th, 2017



Problem Description

The goal of this project is to design a safe and convenient bicycle access corridor between Georgia Tech's West Campus and Atlanta's Westside neighborhood.



Existing Conditions

Primary Intersections - Along Northside Drive


- 10th Street / Northside Drive
- 8th Street / Northside Drive
- PATH Parkway / Hampton Street / Northside Drive

Development

- Existing
- Planned



Primary Intersections - Along Northside Drive






Existing Conditions - Development

Residential

- o (1) Arium Westside
- o (2) 1016 Lofts
- o (3) 935M Apartments
- (4) M Street Apartments
- o (5) The Brady Apartments

Commercial

- Retail
- Breweries
- Coffee boutiques







Planned Development

10th Street at Northside Drive

- Installation of designated bicycle path and multi-use path
- Along corner of 10th Street and Northside Drive







Project Stakeholders

Designers

- Transplant Design, LLC
- Georgia Tech Capital Planning and Space Management (GTCPSM)
- PATH Foundation

Protectors

- Georgia Tech Police Department (GTPD)
- Atlanta Police Department (APD)

Users

- Bicycle Infrastructure Improvements Committee (BIIC)
- Other cyclists and pedestrians



Transplant's Design Alternatives

Georgia Tech's Bicycle Master Plan

- 8th Street Bicycle Boulevard
- Connection of Northside Drive to Hemphill Avenue

Four Design Alternatives

- 8th Street Connection to PATH Parkway
- Overpass Across Northside Drive
- Curran Street Connection to PATH Parkway
- Signalized Bicycle Path Across Northside Drive



Transplant's Design Alternatives

Georgia Tech's Bicycle Master Plan

- 8th Street Bicycle Boulevard
- Connection of Northside Drive to Hemphill Avenue

Four Design Alternatives

- 8th Street Connection to PATH Parkway
- Overpass Across Northside Drive
- Curran Street Connection to PATH Parkway
- Signalized Bicycle Path Across Northside Drive

One Grand Idea

Incorporating one of the four alternatives into the envisioned 8th Street Bicycle

Boulevard



8th Street
Connection to
PATH Pkwy




Overpass Across Northside Drive

- Grade-separated bikeway and pedestrian
 bridge accommodating two lanes of bicycle
 traffic
- 5% grade recommended by AASHTO
 Guidelines
- Return to grade along the north edge of WR29 parking lot on Georgia Tech's campus






Curran Street
Connection to
PATH Parkway





Signalized Bicycle
Path Across
Northside Drive






One Grand Idea - 8th Street Bicycle Boulevard

8th Street Bicycle Boulevard

- Two-way designated bicycle path painted onto existing roadway
- Replaces existing on-street parallel parking
- Extends entire length of 8th Street between
 Hemphill Avenue and Curran Street





Alternative Evaluation Parameters

Comparative analysis with summation score: lowest = best

Parameter	8th Street Connection to PATH Parkway	Overpass Across Northside Drive	Curran Street Connection to PATH Parkway	Signalized Bicycle Path Across Northside Drive
Connectivity	3	1	4	2
Construction Cost	2	4	1	3
Safety	3	2	1	4
Alignment w/ GT Bicycle Master Plan	2	4	3	1
Design Constraints	2	4	1	3
TOTAL:	12	15	10	13


Proposed Alternative Selection


Comparative analysis with summation score: lowest = best


Parameter	8th Street Connection to PATH Parkway	Overpass Across Northside Drive	Curran Street Connection to PATH Parkway	Signalized Bicycle Path Across Northside Drive
Connectivity	3	1	4	2
Construction Cost	2	4	1	3
Safety	3	2	1	4
Alignment w/ GT Bicycle Master Plan	2	4	3	1
Design Constraints	2	4	1	3
TOTAL:	12	15	10	13



Design of Proposed Alternative








Overall View 1 View 2



Design of Proposed Alternative





Design of Proposed Alternative





Project Costs


- Demolition
- Construction
 - Traffic Rerouting
 - Ancillary Costs
 - Labor Costs
- Summary of Probable Project Costs



Demolition



Curb and gutter removal



Tree removal



Construction

Repainting Curran St & 8th St

Bicycle path

Extending sidewalk







Summary of Probable Project Costs

Curran Street Connection to PATH Pa	rkway						
Demolition and Site Clearance							
Expenditure	Quantity	Roundup	Unit	Unit Price	CF	Item Total	Group Total
Curb and gutter	52.5	60	LF	\$5	10%	\$330	
Clearing / grubbing	0.19	0.5	AC	\$3,000	10%	\$3,300	
Erosion Control	0.19	0.5	AC	\$7,500	10%	\$8,250	
							\$11,880
Construction							
Expenditure	Quantity	Roundup	Unit	Unit Price	CF	Item Total	Group Total
Concrete Sidewalk	250	250	SY	\$46.00	10%	\$11,500	
Heavy Duty Asphalt Pavement	666	670	SY	\$36.00	10%	\$24,120	
Pavement striping	1505.17	1510	LF	\$12.00	10%	\$18,120	
Bollards	4	5	EA	\$800.00	10%	\$4,000	
Signage	10	10	EA	\$100.00	10%	\$1,000	
							\$58,800
Total Cost for Demolition, Site Clearance, and Construction			\$70,700			- 1	


Traffic Control - Phase 1




Existing traffic patterns



Traffic Control - Phase 2




Existing traffic patterns






Traffic Control - Phase 3



Existing traffic patterns



Probable Schedule of Completion

	Time After Project Start (weeks)				
Project Category	0-3	3-6	6-9	9-12	12-15
8th Street Repainting	Traffic Control - Phase I	Traffic Control - Phase II			
Curran Street Repainting			Traffic Control - Phase III		
PATH Parkway Extension	Clear vegetation, begin regrading	Regrade and flatten any remaining areas of need	Pave new paths	Create crosswalk at the intersection of expanded PATH Pkwy over Tech Pkwy	Install landscaping per GT Landscape Master Plan. Install GT standard lighting.



Summary

<u>Problem Statement:</u> The goal of this project is to design a safe and convenient bicycle access corridor between Georgia Tech's West Campus and Atlanta's Westside Neighborhood.

Proposed Design: Curran Street connection to PATH Parkway

Probable Project Cost: \$70,700

Probable Schedule of Completion: 12-15 weeks





